| | | | | | |
|---|---|---|---|---|---|
| 5 | 93.06 | Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed cement concrete for beams,columns, staircase and roof with M20 RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc, including smooyh finish in CM 1:3, with all lead and lift etc., complete.(exculsive of cost of steel and fabrication charges) | cum | 6789 | Rupees Six Thousand Seven Hundred Eighty Nine Only |
| 6 | 56.63 | Providing T.M.T steel reinforcement for Bars Fe 415 R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and/ or welding wherever requred, tying with binding wire and anchoring to the adjoining members wherever nacessery complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications | qtl | 7747 | Rupees Seven Thousand Seven Hundred Forty Seven Only |
| 7 | 537.72 | Providing and fixing pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 Plastering and finishing cutting etc., complete. Of size 450x200x400 mm | nos | 332 | Rupees Three Hundred Thirty Two Only |
| 8 | 237.6 | Covering Slab(As per Data Rate approved 100mm thick) | sqm | 1469 | Rupees One Thousand Four Hundred Sixty Nine Only |
| 9 | 92.4 | Providing and applying ready mix priming coat over concrete/ manosry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per spcaifications. | sqm | 25 | Rupees Twenty Five Only |
| 10 | 92.4 | Providing and applying Spary painting in coats(excluding priming coat ) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surfaces of all dirt dust and other foreign matter, and sand papering including cost of materials, labour, Complete as per specifications. | sqm | 63 | Rupees Sixty Three Only |

Executive Engineer
Rajarajeshwarinagar Division
B.B.M.P

Scanned by CamScanner